



# North/West Passage Work Zone Management Practices for I-90/I-94

Project Webinar

April 26, 2017

***TODAY'S WEBINAR WILL BE RECORDED***



# Agenda

1. Introductions
2. North/West Passage Overview and Project Purpose
3. Summary of North/West Passage State Work Zone Management Practices  
*Presenter: Tina Roelofs, Athey Creek*
4. Minnesota DOT I-94 IWZ Experience  
*Presenter: Tom Dumont, MnDOT*
5. Iowa DOT IWZ Contracting and Experiences  
*Presenter: Tim Simodynes, Iowa DOT*
6. Focused Discussion on North/West Passage Work Zone Management Topics



# North/West Passage Overview

- North/West Passage has been a Transportation Pooled Fund since 2003
- Members
  - 7 States from Washington to Minnesota along I-90 and I-94





# North/West Passage Overview

- States share common challenges
  - Commercial and recreational travel corridor
  - Extreme weather conditions
  - Road closures and transportation management
- North/West Passage vision is to develop effective **methods for sharing, coordinating, and integrating** traveler information and operational activities across borders



# Project Background

- From 2010-2014, there were 42 fatal crashes in work zones on Interstate routes within the North/West Passage states
- Work zone management practices continue to evolve, particularly those involving the use of technology
- Effective work zone management improves both safety and mobility for travelers



# Project Purpose

---

Identify work zone management practices (including technology used in work zones) that are being used among the NWP states for road work projects that significantly impact travel along the I-90/I-94 Corridor.



# Project Approach

- Review and summarize national information and resources on work zone management practices
- Interview North/West Passage states
- Conduct a webinar to highlight work zone practices
- Develop a Final report



# **Summary of North/West Passage State Work Zone Management Practices**

*Presenter: Tina Roelofs, Athey Creek*





# North/West Passage Interviews

- **Idaho Transportation Department**

*Justin Wuest*

- **Montana DOT**

*Mike Miller and Jim Wingerter*

- **North Dakota DOT**

*Brandon Beise, Doug Schumaker, and Travis Lutman*

- **Minnesota DOT**

*Adam Wellner and Jeff Rieder, District 6*

*Tom Dumont, District 3*

- **South Dakota DOT**

*Christina Bennett*

- **Washington State DOT**

*Steve Haapala*

# Purpose of Interviews

---

- What WZ management practices have been used on I-90/I-94 (and other interstates)?
- What Intelligent Work Zone (IWZ)/Technology applications have been used?



# Idaho Highlights

- IWZ/Technology Applications
  - Speed Detection Signs to slow down traffic through work zones
  - Installed WiFi detectors at the top of Lookout Pass on the Idaho-Montana line to observe vehicle travel times to internally discuss modifications
- Lookout Pass has many cyclists who were restricted from crossing during construction so ITD shuttled cyclists through the work zone since there was no good detour for them




# Idaho Highlights

- I-90 from Washington to Coeur d'Alene
  - Heavily traveled
  - Typically complete work at night to minimize delay
  - Full reconstruction project - Summer 2017
    - Work can't all be completed at night
    - Considering:
      - Crossovers to prevent long queues
      - Incorporate technology (e.g. communication to VMS)

# Montana Highlights

- Work Zone Practices
  - Completes most construction projects and highway maintenance during daylight hours
  - Work Zone Safety and Mobility Toolbox
    - Provides guidance, design tools, design training and construction tools





# Montana Highlights

- IWZ/Technology Applications
  - Arrow boards for maintenance (mandatory)
  - LED lights on the outside edge flagger signs
  - Tried intrusion alarms on cones but found construction zone noise prevented alarms from being heard
  - Portable VMS to alert motorists of lane closures
  - Speed message board to alert motorists they are entering work zone too fast
  - Starting to implement the zipper merge

# Montana Highlights

- Steel Bridge Rehab Project: Northbound I-15 over the Missouri River
  - Reduced speed from 70 mph to 35 mph
  - Technology
    - Portable arrow boards
    - CMS
    - Speed display
      - Increased driver compliance



Approach Speed Display



Slow Down Display



# North Dakota Highlights

---

## Work Zone Practices

- Handbook
  - Standard layouts for short term work (maintenance)
  - Standard general traffic management practices
- Typically work is complete during the day





# North Dakota Highlights

---

## IWZ/Technology Applications

- Used BlueTOAD to provide website of current and historic travel times of a project in Fargo
- Explored using dynamic merge and queue warning but benefit/cost prohibits until technology costs decrease further
- Considering using smart cones and currently working with a vendor to get vibrating wrist bands for workers
- Portable DMS signs may be used in work zones when available



# Minnesota Highlights

---

## I-90 Work Zone Practices

- Lowest volume expressway in southeastern district
- Plenty of capacity even with lane closures
- Use static signing for zipper merge on I-90
- In the process of developing a Lane Closure Manual for smaller volumes of traffic (similar to the manual used in the Twin Cities area)




# Minnesota Highlights

## I-35 and US 52

- Higher volume roadways
- Dynamic speed limits
  - Only activated when vehicles were within a certain distance of a work crew.
- Queue warning system
- Dynamic zipper merge
- Established alternate route with permanent signing for I-35 to use during emergencies, construction and maintenance
  - Alternate route has also been identified for I-90 to address bridge crossings (won't permanently sign, but shared with law enforcement, local road authorities etc. for pre-established detours)

# Washington Highlights

- Work Zone Practices
  - Median crossovers
  - Avoid work zones during peak hours, complete work at night
  - Maintain full lanes during peak hours
  - Design Manual





# Washington Highlights

---

- IWZ/Technology Applications
  - Variable speed limits
  - Queue warning system
    - Shadow vehicle with a VMS to alert motorists in advance of slow or stopped traffic
  - More IWZ used around Seattle area



# South Dakota Highlights

---

- Work Zone Practices
  - Restrict lane closures along interstates to 3 miles
- IWZ/Technology Applications
  - Interested in radar speed and motorist feedback board to encourage drivers to slow down
  - Interested in Smart Cones to track vehicle speeds to determine if extra law enforcement is needed



# South Dakota Highlights

- Sturgis Rally
  - Avoid construction and maintenance in the area during the Rally
  - Last year there were high traffic volumes on the interstate causing stopped traffic
    - Used queue detection system to warn motorists

# Summary


- NWP states are using IWZ/Technology in work zones
- Lower volumes in rural areas may not warrant some applications
- However, DOTs are willing to use IWZ/technology if it is cost effective



**Minnesota DOT I-94**  
**Intelligent Work Zone Experience**  
*Presenter: Tom Dumont, MnDOT*

## District 3

- 12 Counties
- Central Minnesota
- I-94 - 90 miles
- Baxter – headquarters
- St. Cloud – sub area



# Traffic Control Impacts

## 1. Significant Impact

– Over 30,000 ADT

- Lane restrictions/night work
- Traffic rerouted

## 2. Non-Significant Impact

– Under 30,000 ADT

- Completed under traffic
- Restrictions/night work?
- Depends type of Construction

# Types of Construction

## ➤ Bituminous

- Done under traffic
- Work/Lane restriction may apply - night

## ➤ Concrete

- Joint rehab may be done under traffic/night
- Overlays/Reconstruction – Traffic rerouted onto opposing lanes

# Data Collection

- ADTs
  - 10% for peak hour estimation
  - 60/40 direction flow
- Hourly count data
  - Tube counts
  - Existing count stations
  - Adjust for time of year
    - Month, Weekends, etc.

# Capacity Thresholds

- 1,500 vph at lane drop
  - Rural 2 =>1 lane drop
  - No construction friction
- 1000 vph if construction “friction”
  - Less capacity inside construction zone due to “friction” activities.

# Demand vs Capacity

- Demand vs Capacity (1500)
  - Queueing/Delay Analysis
  - Feasibility of alternate routes
  - 10% diversion
  - Seasonal Traffic – +15% on weekends
  - Holiday weekends
- Impacts determine IWZ efforts

# Intelligent Work Zone (IWZ) efforts

- Active Zipper Merge/Use Both Lanes
- Stopped Traffic
- Travel Times
- 511
- Dynamic Detour
- ❖ Combination



# I-94 Project

## Un-bonded Concrete Overlay

- SP 7380-238
- Clearwater to St. Cloud
- Spring 2013
- 7.5 miles length
- \$16.5 M



# I-94 Traffic Volumes

- Average Daily Traffic (ADT)
  - 45,500 (M-Thur)
  - 55,000 (Average Weekends)
- Hourly volumes
  - Peak periods – 2,400 – 2,800 VPH
- Single Lane Capacity
  - 1,500 VPH – merge area
  - 1000 vehicles per hour over capacity

## ❖ Significant Delays/Backups


- Traffic Management Plan

# Traffic Management Plan


- Significant Impact Project
- Traffic Management Plan (TMP)
  - 1 – Traffic Control Plans
  - **2 – Traffic Operations Plan**
  - 3 – Public Information Plan
- TMP – revisit scope of project
  - Concrete – due to material life span

## TH 94 WB Monthly Averages on Fridays

Assumed Detour Reduction of 10%



Assumed Capacity of 1500 and Detour Reduction of 10%



# Traffic Control Plans

- Crossover/one lane traffic
  - Head-to-head
- Ramp closures/detours
  - Ramps/loops/TH 24
- Hwy 24 Dynamic Detour

# Staging

- Fall of 2012 prep work
  - Under lane closures (restricted times)
    - Crossovers
    - Emergency pull offs
    - Ramp gore work
- Spring 2013
  - Main construction – concrete un-bonded
  - Head-to-head

# Staging

2013

☐ Stage 1 – EB closed (Traffic on WB lanes)

☐ April to Memorial (Memorial weekend open)

☐ Stage 2 – WB closed (Traffic on new EB lanes)

☐ Memorial to July 4<sup>th</sup> (July 4<sup>th</sup> weekend open)

☐ Stage 3 – Clean up and removals

❖ Incentives for Stage completion




# ***IWZ Project SP 8823-260 Traffic Operations***

**IWZ – Separate from  
construction project**

## **IWZ Tool Box**

- I. Travel Time Info**
- II. Stopped Traffic**
- III. TH 24 Detour -**
  - **Dynamic**
  - **I-94 WB traffic  
30% exit TH 24  
CSAH 75 detour**




# IWZ Contract Procurement

Why?

- Better management of IWZ application - Disincentives
- Time for Integration with RTMC
- Operational checks prior to construction
- Technical IWZ expertise

# ESTIMATED TRIP TIME




Consideration should be given to posting an alternate route and travel time for additional driver information.

- The CMS may be replaced with static warning signs equipped with two (2) CMS characters in dynamic mode. The characters would display the real-time travel time in the work zone downstream.
- Consideration should be given to posting an alternate route and travel time for additional driver information.
- The CMS may be supplemented with other informational devices such as Highway Advisory Radio (HAR).



## NOTES

- Advance warning signs and other standard temporary traffic control devices have not been shown on this figure. Refer to the MUTCD including the 2007 Field Manual or the TTC Layout Templates for typical layout examples.
- All IWZ Guide Signs and CMS should be reviewed by the Mn/DOT Office of Traffic Safety, & Operations for design and message approval.
- Approved CMS messages should be listed in the Special Provisions, and approx CMS locations should shown on the TTC plans. All CMS displays should be blank when messages are not warranted.
- Refer to the Toolbox Definitions Section for graphic symbols and terms.



- The CMS may be replaced with an appropriate warning sign equipped with dynamically automated flashing lights as shown below.
- The static signs are spaced incrementally and the individual flashers are activated in response to queued traffic when the queue is detected within one mile of the sign location.



- When traffic queue lengths are reasonably predictable, warning motorists of stopped / slowed traffic may be accomplished with the use of typical TTC warning signs placed prior to the anticipated beginning of queue.
- The system may be combined with "Dynamic Merge" and "Stopped Traffic Advisory" systems

## NOTES

- Advance warning signs and other standard temporary traffic control devices have not been shown on this figure. Refer to the MN MUTCD including the 2007 Field Manual or the TTC Layout Templates for typical layout examples.
- All IWZ Guide Signs and CMS should be reviewed by the Mn/DOT Office of Traffic, Safety, & Operations for design and message approval.
- Approved CMS messages should be listed in the Special Provisions, and approx CMS locations should shown on the TTC plans. All CMS displays should be blank when messages are not warranted.
- Refer to the Toolbox Definitions Section for graphic symbols and terms.

# Existing ITS infrastructure

- Leverage existing ITS infrastructure
- St. Cloud east to Twin Cities
  - Fiber network
  - Connected to RTMC
  - Detectors/Cameras (1.5 mile spacing)
- St. Cloud west
  - No ITS infrastructure



# IWZ Concept Plan Development

## 1. Travel Time

- A. MNDOT provided WB information
- B. IWZ contractor provided EB information
  - 2 signs each direction
  - 10 and 15 miles prior to project
  - Detector spacing every mile (20 total)

## 2. Stopped Traffic Advisory

- CMS every 3 miles (8 total)
- 2 boards active prior to slow/stop point
- 40 mph slow & 15 mph stopped threshold

# IWZ Concept Plan Development

## 3. Hwy 24 Dynamic Detour

- 1 CMS prior to Hasty interchange
  - Use CSAH 75 alternate route WB
- Approx. 5 miles east of project
- Activated when backups started Hwy 24
- 1000 vph less on I-94 WB peak times

## 4. Weekly IWZ meetings





# Concept ITS Plan

concept plan.pdf - Adobe Reader

File Edit View Window Help



PLOTTED/REVISED 06-SEP-2002


PLAN NUMBER / PROJECT NAME / COUNTY / DISTRICT / SHEET NO.

## MINNESOTA DEPARTMENT OF TRANSPORTATION

CONSTRUCTION PLAN FOR INTELLIGENT WORK ZONE SYSTEM

LOCATED ON T.H. 94 FROM R.P. 156+00.000 TO R.P. 192+00.500

STATE PROJ. NO. 8823-260 (T.H. 94)  
GROSS LENGTH 132720.00 FEET 36.500 MILES  
BRIDGES-LENGTH N/A FEET N/A MILES  
EXCEPTIONS-LENGTH N/A FEET N/A MILES  
NET LENGTH 132720.00 FEET 36.500 MILES  
REF. POINT 156+00.000 TO REF. POINT 192+00.500



FED. PROJ. NO. STATE FUNDS

### GOVERNING SPECIFICATIONS

THE 2003 EDITION OF THE MINNESOTA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR CONSTRUCTION, SHALL GOVERN.

### INDEX

SHEET NO.	DESCRIPTION
1	TITLE SHEET
2	ESTIMATED QUANTITIES
3 - 5	SIGNING PLAN
6	SIGN INSTALLATION SHEETS

THIS PLAN CONTAINS 6 SHEETS

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

PRINT NAME: LICENSE #  
DATE: SIGNATURE:  
DESIGN SQUAD:

I HEREBY CERTIFY THAT THE FINAL FIELD REVISIONS, IF ANY, WERE PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

PRINT NAME: LICENSE #  
DATE: SIGNATURE:

DATE	SHEET NO.	APPROVED BY




PROJECT LOCATION  
COUNTY: STEARNS AND WRIGHT  
DISTRICT 438 ST. CLOUD

STATE PROJ. NO. 8823-260 (T.H. 94) SHEET NO. 1 OF 6 SHEET

# Concept ITS Plan

concept plan.pdf - Adobe Reader

File Edit View Window Help



POSTED DECEMBER 1997	AGENCY ADVANCE WARNING STATION MILES	TRAIL LENGTH MILES	SPACING OF CHANGING OVERLAYS MILES	BUFFER ZONE MILES	DEGREE OF CLOSURE DISTANCE
IMPH	FEET	FEET	FEET	FEET	FEET
0 - 30	250	200	25	85	500
30 - 40	325	300	25	170	700
40 - 50	600	600	50	300	1000
50 - 60	750	700	50	555	1200
60 - 85	1000	800	50	885	1400
85 - 100	1200	1000	50	1000	1600

**NOTE:**

NOT ALL INFORMATION IN THIS BOX MAY APPLY TO THIS DETAIL.

Eastbound			Westbound		
Ref. Pt.	DMS	Detector	Ref. Pt.	DMS	Detector
154.83	1	0	178.0	0	0*
156.00	0	1	179.5	0	0*
157.00	0	1	180.7	0*	0*
158.00	0	1	181.5	0	0*
159.00	1	1	182.5	0	0*
160.00	0	1	183.5	0	0*
161.00	0	1	184.5	0	0*
161.50	0	1	185.5	0	0*
162.00	0	1	186.5	0*	0*
163.00	0	1	187.5	0	0*
164.00	0	1	188.5	0	0*
165.00	1	1	189.5	1	1
166.00	0	1	190.5	0	1
167.00	0	1	191.5	0	1
168.00	1	1	192.5	1	0*
169.00	0	1	193.8	0*	0
170.00	0	1	206.7	0*	0
171.00	0	1	210.65	0*	0
<b>Totals</b>	<b>4</b>	<b>16</b>		<b>3</b>	<b>3</b>

Within Construction Area			Within Construction Area		
171.75	0	0*	171.75	0	0*
173.00	0	0*	173.00	0	0*
174.50	0	0*	174.50	0	0*
175.50	0	0*	175.50	0	0*
176.75	0	0*	176.75	0	0*
178.00	0	0*	178.00	0	0*

Plotter:


\* in-place devices

NOTES:

- ① FURNISH & INSTALL
- ② INSTALL STATE SUPPLIED NON-INTRUSIVE DETECTION MOBILE DETECTION. SEE SPECIAL PROVISIONS FOR CONTACT INFO.
- ③ INPLACE SIGNS
- ④ INPLACE DETECTORS

DYNAMIC STOPPED TRAFFIC ADVISORY  
LEFT LANE CLOSURE  
MULTI-LANE DIVIDED ROAD

# Concept ITS Plan



# Location of DMS and Detectors

Number and Location of Dynamic Message Signs and Mobile Detectors					
Eastbound			Westbound		
Ref. Pt.	DMS	Detector	Ref. Pt.	DMS	Detector
154.83	1	0	178.0	0	0*
156.00	0	1	179.5	0	0*
157.00	0	1	180.7	0*	0*
158.00	0	1	181.5	0	0*
159.00	1	1	182.5	0	0*
160.00	0	1	183.5	1	0*
161.00	0	1	184.5	0	0*
161.50	0	1	185.5	0	0*
162.00	0	1	186.5	0*	0*
163.00	0	1	187.5	0	0*
164.00	0	1	188.5	0	0*
165.00	1	1	189.5	1	1
166.00	0	1	190.5	0	1
167.00	0	1	191.5	0	1
168.00	1	1	192.5	1	0*
169.00	0	1	195.8	0*	0
170.00	0	1	206.7	0*	0
171.00	0	1	210.65	0*	0
Totals	45	16		3	3


  

Within Construction Area			Within Construction Area		
171.75	0	0*	171.75	0	0*
173.00	0	0*	173.00	0	0*
174.50	0	0*	174.50	0	0*
175.50	0	0*	175.50	0	0*
176.75	0	0*	176.75	0	0*
178.00	0	0*	178.00	0	0*


Notes:

\* = inplace devices

# Concept IWZ Plan



# Concept IWZ Plan







# I-94 EB

17 miles to crossover (first static sign)





# I-94 EB

## 2<sup>nd</sup> static sign



# I-94 EB

## 3<sup>rd</sup> sign hybrid (17 miles to crossover)



# I-94 EB

4<sup>th</sup> sign hybrid (10 miles to crossover)





# Nonintrusive Detector

## 1 mile spacing



# I-94 WB

## Travel time (MnDOT)



# I-94 WB

## Travel time (MnDOT)



# Data Collection

- Weekly data collected and meetings
  - Speeds
  - Travel times
  - Message content
    - Travel time postings
    - Stopped message posting
  - Compare to field information




Greater than 40 mph
Less than 40 mph, greater than 30 mph
Less than 30 mph, greater than 15 mph
Less than 15 mph

Eastbound Detector Speeds

	Avon				St. Joseph				TH 23				TH 15				CSAH 75			
	Q1	Q2	Q3	Q4	Q5	Q6	Q7	Q8	Q9	Q11	Q12	Q13	Q14	Q15	Q16	Q17	Q18			
6/14/13 2:00 PM	73	69	73	74	76	69	67	73	71	70	72	74	70	20	46	57	59			
6/14/13 2:15 PM	73	68	74	75	77	70	69	73	72	70	71	74	70	21	37	58	57			
6/14/13 2:30 PM	74	69	73	73	76	70	68	73	72	71	72	73	46	19	36	57	57			
6/14/13 2:45 PM	74	69	76	76	78	70	69	74	73	71	72	76	23	19	40	59	57			
6/14/13 3:00 PM	73	68	73	73	78	71	69	74	73	71	72	73	27	16	48	59	58			
6/14/13 3:15 PM	73	68	74	73	78	71	68	73	72	72	73	73	34	20	33	59	58			
6/14/13 3:30 PM	73	67	74	74	78	70	68	73	73	71	71	73	16	13	32	60	47			
6/14/13 3:45 PM	73	68	73	74	74	69	68	73	72	71	72	73	12	20	32	57	53			
6/14/13 4:00 PM	72	67	73	74	76	69	67	72	72	71	72	73	13	13	24	50	50			
6/14/13 4:15 PM	72	68	74	74	77	70	68	73	72	70	71	73	28	19	11	10	33			
6/14/13 4:30 PM	73	68	74	74	73	70	68	73	72	70	71	74	7	8	14	16	33			
6/14/13 4:45 PM	74	69	73	74	78	70	68	73	73	71	72	69	4	12	20	17	26			
6/14/13 5:00 PM	74	69	73	73	76	70	68	73	72	72	72	31	9	13	22	19	32			
6/14/13 5:15 PM	74	70	73	76	77	70	68	74	73	71	72	26	7	13	23	16	34			
6/14/13 5:30 PM	74	69	74	73	77	70	68	73	73	71	73	28	10	14	27	23	32			
6/14/13 5:45 PM	74	70	73	74	78	69	68	73	72	72	72	63	6	12	22	17	32			
6/14/13 6:00 PM	74	70	76	76	80	70	69	73	74	71	73	30	7	17	35	28	33			
6/14/13 6:15 PM	73	69	74	76	78	69	67	73	73	72	73	36	12	19	39	13	32			
6/14/13 6:30 PM	74	70	76	73	76	70	70	73	71	71	72	68	5	12	40	12	31			
6/14/13 6:45 PM	74	70	76	73	76	71	69	73	73	72	73	37	14	22	39	13	33			
6/14/13 7:00 PM	74	70	73	76	77	71	69	73	72	72	72	74	19	10	32	14	33			
6/14/13 7:15 PM	74	70	73	73	76	71	69	74	73	71	73	76	33	10	27	18	34			
6/14/13 7:30 PM	74	70	73	77	78	70	69	74	74	72	74	73	64	13	39	18	33			
6/14/13 7:45 PM	74	70	76	76	78	72	69	74	74	71	74	73	71	19	35	12	36			
6/14/13 8:00 PM	74	70	76	76	76	71	68	73	73	72	72	74	71	11	43	15	34			
6/14/13 8:15 PM	74	70	77	73	79	72	70	74	73	72	73	76	71	63	50	16	36			
6/14/13 8:30 PM	74	70	73	74	76	71	70	74	74	72	73	73	73	63	50	14	37			
6/14/13 8:45 PM	74	70	76	77	79	72	70	74	73	72	73	74	71	64	63	27	32			
6/14/13 9:00 PM	74	68	73	73	77	71	69	74	73	72	72	74	71	64	72	64	36			
6/14/13 9:15 PM	73	68	76	73	76	69	67	73	72	72	73	74	71	66	73	64	50			
6/14/13 9:30 PM	74	68	74	73	76	70	69	73	72	71	72	73	71	66	72	62	46			
6/14/13 9:45 PM	72	68	72	72	74	69	68	73	72	70	72	72	71	64	72	61	41			
6/14/13 10:00 PM	72	68	74	73	73	70	68	71	70	71	72	74	70	66	74	59	59			
6/14/13 10:15 PM	71	68	73	72	74	68	69	72	70	70	72	72	71	63	73	59	62			
6/14/13 10:30 PM	72	69	74	76	78	69	68	73	71	70	71	74	71	63	72	60	63			
6/14/13 10:45 PM	73	68	74	73	78	70	66	73	72	71	72	73	71	63	73	63	62			
6/14/13 11:00 PM	71	68	74	74	73	67	68	72	70	71	72	73	70	67	72	62	63			



# Travel Time TT17 Friday 6/14/2013



# Concerns

- Costs – 20 detectors
  - I-35 Duluth 6 detectors/\$395,000
  - \$500,000 - ????
- Integration
- Accuracy of information – length

# IWZ Costs

- Lower than expected
  - \$250,000 range
- 2 Interested Bidders
  - Safety Signs – awarded contract
    - ASTI subcontractor
    - Good to work with

# Project Findings

- Integration – smoother than expected
- Contractor - open to improvements
- Backups less the expected (4-5 miles)
- Diversion of traffic – up to 1000 vph
  - TH 24 detour
  - TH 10 – good parallel route WB
  - CSAH 75 parallels I-94
  - Limited public complaints

# Project Findings

- Weekly meetings were good
- Speed variations during hour
  - More averaging speed data – less jumping
- Contractor's web site
  - Good to monitor backups
  - Hybrid signs – Display

# Questions



# **Iowa DOT Intelligent Work Zone Contracting and Experiences**

*Presenter: Tim Simodynes, Iowa DOT*



# ***Traffic Critical Projects & Intelligent Work Zones in Iowa***

*for North/West Passage*

*Tim Simodynes*

*Office of Traffic Operations*

*April 26, 2017*





# Focus on Traffic Operations

## Address Sources of Congestion

- Recurring Congestion
- Incidents / Crashes
- Weather
- Special Events
- **Construction**


***“Traffic Critical  
Projects”***

*(2014)*



# Iowa Inventory

## 9 “Metro” Areas (over 50,000)



# Iowa DOT Permanent ITS



380 PTZ Cameras



75 Overhead DMS



53 Side-Mount DMS



370 Side-Fire Radar Traffic Sensors

Communications  
Fiber Optic +  
Wireless Radios or  
Cellular Modems



Highway  
Advisory Radio  
(HAR)  
Transmitters



# Statewide Traffic Management Center (TMC)



- Moved to Ankeny in 2015
- 24/7 Operation
- TransSuite ATMS software





# TransSuite ATMS



- Controls Cameras, DMS & Sensors
- Capable of automated travel times and automated DMS messages
- Able to integrate portable devices



# Intelligent WZ Team (2014-present)

- SRF Consulting: Writing contract and managing program
- Street Smart Rental: Statewide IWZ Device Services contract
- TransCore: ATMS Integration
- Digital Traffic Systems: ITS Maint.
- Kapsch (formerly Schneider/Telvent): Traffic Management Center
- CTRE (Iowa State Univ.): Eval. & Analysis



# Portable Cameras



- Pan-tilt-zoom
- Great within reach of ITS Communications Network
  - Same as permanent Cameras
  - On [511ia.org](http://511ia.org)

Video Streaming more difficult in rural areas (on Cellular Modems)



# Portable Traffic Sensors



- Wavetronix, side-fire radar
- Same as our permanent Sensors
- Traffic counts & speeds every 20 seconds





# Portable DMS




- ALL controlled by TMC since 2013



# Queue Detection Systems

## Southbound I-35



# Interstate Ramp Monitoring



Council Bluffs



# 511ia.org & Mobile App

511 Iowa Department of Trans... X +

hb.511ia.org/#camerasHome?layers=googleTraffic%2Ccameras%2Csigns&timeFrame Search

511 HELP | MORE 511 | TRUCKERS | WINTER DRIVING | BORDERING STATES' 511 | CONTACT Your 511 (sign in)

Text Size A A Text Only View Streamlined Version Future Info: [Calendar Icon]

Layers Traffic Speeds, Cameras, Electronic Signs

Map Satellite [User Icon]

**Menu**

- Personalize your 511
- Travel At-A-Glance
- Incidents
- Construction
- Winter Driving & Incidents
- Plow Cameras
- Cameras & Speeds**
- Twitter
- Facebook

**Ames**

Iowa State University


Ames Municipal Airport-AMW

Legend

Map data ©2017 Google 1 km Terms of Use Report a map error

# Additional IWZ Devices

- Portable DMS with Radar Detection



- Speed Feedback Trailers



# Trucks Entering System



# “Truck Entering” Warning



# “Truck Entering” Warning

I-29 Council Bluffs



*Looking South*



# Traffic Critical Projects

<https://sites.google.com/site/iowatcp>



## TRAFFIC CRITICAL PROJECTS OFFICE OF TRAFFIC OPERATIONS

[HOME](#)[2017](#)[FUTURE](#)[ARCHIVES](#)[CONTACTS](#)[RESOURCES](#)

### About the Traffic Critical Projects Program:

The Traffic Critical Projects (TCP) program identifies key construction projects across the state that may cause significant safety or mobility issues to the traveling public. Using various mitigation methods, the TCP program works to reduce or eliminate any potential safety or mobility concerns.

**PROGRAM  
OVERVIEW**

**IWZ MAP OF  
EQUIPMENT**

**CTRE  
TRAFFIC DATA**


**IWZ  
STRATEGIES**

**ISSUE/CHANGE  
REPORT**


**DOCUMENTS  
/REPORTS**



# *Potential 2017* Traffic Critical Projects



# 2017 IWZ Device Map



# **Traffic (BIG) Data Analysis by Iowa State University**


Center for Transportation Research & Education  
(CTRE)

at the

Institute for Transportation (InTrans)

# REACTOR Web Site

## <https://reactor.ctre.iastate.edu/>







# Weekly Performance



# Daily Performance




# Speed Heatmap






# Sensor Performance



# Hourly Volumes



# **Traffic Critical Projects Expansion**

# Traffic Critical Projects Strategies

## Design

- Accommodate future Maint. & Constr.
- Staging to minimize disruptions
- Restrict lane closures to low-volume times

## Traffic Incident Management (TIM) Planning

- *Law enforcement, emergency responders, DOT, city/county*



# TIM Planning on TCPs

- Reinforce Relationships among Engineering, Enforcement, Emergency Responders
- Share information and awareness
- Have contingency/diversion plans in place



# Traffic Critical Projects Strategies

## On-Site Monitoring

- Traffic Control Monitoring
- Highway Helper-like, Traffic Monitoring

## Speed Harmonization

- Speed Feedback Trailers
- Portable DMS with Radar
- ***Enhanced Enforcement***



# Enhanced Enforcement



*I-35, Hamilton County, 2014*





# Questions?



Tim Simodynes, P.E.

ITS Engineer

Office of Traffic Operations

[tim.simodynes@iowadot.us](mailto:tim.simodynes@iowadot.us)

515.239.1606





- Presenter contact information
  - Brandon Beise, NDDOT, [bbeise@nd.gov](mailto:bbeise@nd.gov)
  - Tina Roelofs, Athey Creek, [roelofs@acconsultants.org](mailto:roelofs@acconsultants.org)
  - Tom Dumont, MnDOT, [tom.dumont@state.mn.us](mailto:tom.dumont@state.mn.us)
  - Tim Simodynes, Iowa DOT, [tim.simodynes@iowadot.us](mailto:tim.simodynes@iowadot.us)
- Additional project information
  - Available at [www.nwpassage.info](http://www.nwpassage.info) under Projects